


panels can be removed on three sides (top included). Stick to box with magnets

in between the plates, a small gap is present. To make the box watertight during the experiment, dukttage is added and removed afterwards

additional bard with adjustable feet: to make son even on its base.



a plate of some sort to durche the inside into an experiment space (below) and an module space (above

Rack to suspend the rail system for the modules from

modules can be hung from here curtain-railing to supend modules from. modules are not as big as the dimensions of the box, so there is space for wiring.